



ORDRELISTE

ANTAL	BART NO	MASK NO	ORDR NO	DATUM
1	1/2 GROSCHOLM	FLYT	SILDEFABR.	6-11-29

  

NR	GJENSTAND	ANTAL	MATERIAL	BEMERKNING
14	NAGLER	DIV.	SMILERN	5/8"
13	PEILEBOX	1	METAL	1 1/2"
12	PEILERØR	1	GALVJERN	1 1/2"
11	LUFTRØR	1	GALVJERN	1 1/2"
10	PINNESKR. 1/2" HUTTERE	20	SMILERN	1/2" x 2"
9	VINKELJERNSTREPE	14	VINKELJERN	2 1/2" x 2 1/2" x .35"
8	FLENSER FOR 1 1/2" RØR	2	STÅLPL.	3/4" TYK.
7	FLENSER FOR 2" RØR	2	—	1/2" "
6	FORSTERKNINGSRING	1	—	1/2" "
5	MANDLÅT	1	—	1/2" "
4	KNEPLATER	4	—	1/4" "
3	SLINGREPLATE	1	—	1/4" "
2	ENDERLATER	2	—	1/4" "
1	SKALPLATER	DIV.	STÅLPL.	1/4" "

1/5 MOSS VERFT & DOKK.  
 Fuel oil tank.  
 BRENDELOLJETANK  
 FOR OLIEFYRINGSANLEG.

SKALA 3/4" = 1' 0"  
 3" = 1' 0"

1/5. Grosholm

TEGNET 44  
 KODERT 11  
 EFTERSET  
 DATUM 6-11-29  
 SKEIPL NR 230  
 LØSE NR 5713

Lloyds Register  
 Foundation  
 W473-0119

TANKENS DIMENS. = 3'-0" x 4'-6" x 11'-0" INDV.  
 TANKENS RUMINDHOLD = 4200 LITER.  
 VEGT AV OLJE = CA. 4000 KG.

