

COPY.

CHRISTIANIA

21.11.24

"M"

GROSHOLM

AZEETEJTID = propeller brackets should be

FIKJOEDPAB = 8" by

FIJOT = 4"

SUPPORTED BY DEEP

AWUTYECVOF = floors and

HORIZONTAL CONNECTIONS

EDFUVEKHZE = at top

ECVOFEDOFS = and bottom

EKHIWERTIW = to your satisfaction stop

EJPIZAWSOT = scantlings double bottom

ECWYJEDBUR = approved as proposed

EFLACCUJUV = for oil fuel

EKAWEAWIXE = subject to ceiling

LAI D ON GROUNDS BEING

EHWYFEFLAC = provided for

USE WHEN ORDINARY CARGO CARRIED

EFZISAWIXE = if ceiling

EHWYFAZMYC = provided riveting

EDGES

AZCYREGXEV = tank top plates may be

AZNUCEDOZY = single riveting but

ECVABEFZIS = alternatively if

AWIXEEHDYL = ceiling not

PROVIDED

EKELMAZCYR = thickness of tank top plates

ECLUMKPUW = increased to

FIWYK = .40

ECVOFECURP = and all

AZMYCEJTID = riveting should be

DOUBLE.



© 2019

Lloyd's Register
Foundation

W473-0208