

W479-0338

C. 7c, 11.28.

FREEBOARD REPORT on the S. S. JOSEPHIC.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to the hatchways on the freeboard deck inside the bridge being to Convention requirements when examined. Efficient closing appliances being provided for all air pipes. The freeing port area on each side in the forward & after wells being increased to 20 sq. ft. The opening above the portable plate in the bridge after bulkhead being satisfactorily closed by shifting boards or other equivalent means. The shifting boards closing the openings in the fore-castle bulkhead being fitted for the full height of the opening, if this is not already the case. Gangway, lifelines, or other satisfactory means of protection for the crew being provided in the after well. The doors of the companionways on the poop deck being repaired to the surveyors satisfaction. Newcastle surveyors should be requested to forward full particulars of the hatches in the bridge space. Assg'd letters to Owners & Newcastle surveyors. copy to Dublin.

© 2019 Lloyd's Register Foundation
A.B. 21/6/32