

S.S. "NAIMES" No. 66729 in the Register Book.

Owners:- Messrs. Glover Bros.

Rule dimensions:- 419.83 x 54.42 x 30.85 to upper deck
38.85 to bridge deck.

Scantling Nos:- 85.27 & 35798

Proportions:- L = 13.6 depths to upper deck
10.8 depths to bridge deck.

This ex-German Steamer was built by Bremer Vulkan in 1907 and was classed 100A in the Germanischer Lloyd Register Book.

She is of the two deck type with a long bridge and poop combined, and a topgallant forecastle.

Six watertight bulkheads only are fitted, as shown on the profile plan, instead of seven bulkheads, as required by the Rules.

The vessel is now under Survey at Newcastle. The Newcastle Surveyors have forwarded a preliminary First Entry Report, together with skeleton plans which have been prepared in the Newcastle Office.

The scantlings and arrangements have been examined and compared with the Rule requirements, and it is found that the framing, double bottom, beams, bottom and side plating, and the decks are equivalent to the Rule requirements.

It is submitted that the vessel is worthy to be favourably recommended to the Committee for the 100A-class, a suitable notation being made in the Register Book for the omission of a bulkhead.

If the figure 1 is desired, the Surveyors should forward full particulars of the equipment now on board, and they should be informed that the equipment letter is at. (See separate endorsement for omission of bulkhead.)

dr. 1.7.21
and 8th
3 plans

2977

W.L.

W.L.

W.L.

R.M.M.

8.7.21.

W48-0203