

S.S. "HERA".

It is submitted the freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to:-

- 1) An efficient steel cover of strong construction being fitted to the forward cargo hatchway on the freeboard deck.
- 2) The fidley grating covers being of steel and permanently attached if this is not already the case.
- 3) The doors to the crew's companionways on the poop deck being made efficient to the Surveyor's satisfaction.
- 4) Efficient means of closing being provided for all air pipes and ventilator coamings, except where this is already the case.
- 5) The fore and aft gangway being efficient and of substantial construction and to the Surveyor's satisfaction. The Surveyor should forward to this Office a sketch shewing full details of the gangway's structure.
- 6) 50% of the length of the bulwarks on each side of the forward and after wells being cut away and replaced by open rails, or alternatively the freeing port area on each side being increased to 84 and 103½ square feet in the forward and after wells respectively.

EA. 87B

Convention.

24. 5. 32.

*Asst Mtr.
C. J. P. R.
25/5/32*



© 2019

Lloyd's Register
Foundation

W486-0094