


FREEBOARD REPORT on the M.V. SEMINOLE

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to .

- ✓ (1) efficient means of closing being provided for all ventilators
- ✓ (2) efficient means of closing being provided for all air pipes not fitted with gauze.
- ✓ (3) continuous fore & aft stanchions being fitted on each side of the fore & aft gangway & efficiently connected to the tops of the gangway supports.
- ✓ (4) the bulwarks in the forward well being cut away for half the length of the well & open rails being fitted in lieu thereof.

ention - Tanker

*Ass. M. H.
owners 13/6*



© 2020

Lloyd's Register
Foundation