

FREEBOARD REPORT on the S S CARNARYONSHIRE

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, Subject to

- (1) Efficient means of closing being provided for all air pipes.
- (2) Suitable provision being made for rigging lifelines which should be available for use in all parts of the ship which might have to be used by the crew in the regular working of the vessel
- (3) Steel covers, permanently attached in their proper positions being fitted over the fiddley gratings on the casing top.
- (4) The freeing port area in the forward well being increased to $12\frac{1}{4}$ sq ft each side & that in the after well to $13\frac{1}{2}$ sq ft each side.

Also the Owners
+ M.L.L.
28/9/32

CONVENTION
3 Plans to return to Mr. Wilmot, Marine Capt. Dept. Royal Mail.

67B.
2020
H.S.N.
27. 9. 32

Lloyd's Register
Foundation