

s.s. "ELSIE ANNIE"

It is submitted the freeboards given on the accompanying form, being those required by the Tables, for approval, subject to:-

- (1) All the wood side fore-and-afters in the cargo holdways being renewed and made equal to the Convention requirements, and being steel shod,
- (2) The bearing surface for the hatchway fore-and-afters being increased to 3 inches,
- (3) The hatch covers being repaired or renewed to Surveyor's satisfaction,
- (4) One deadlight being supplied in the forecastle, *no* one missing,
- (5) Gangways, lifelines or other equivalent means for the protection of the crew being provided in the well. *Suitable provision*
- (6) The freeing port area in the raised quarter deck marks being increased to 13 sq. ft. on each side of the p.
- (7) The wood door on the raised quarter deck giving direct access to the engine space being replaced by a hinged steel door capable of being operated from both sides. *no*
- (8) the closing appliances on the doors being *machinery every forecabin* repaired to the Surveyor's satisfaction.

vention.

S.T.B.
6-4-32

*present letter
to Owners
6/4/32*



© 2020

Lloyd's Register
Foundation

W494-0215