

FREEBOARD REPORT on the S PUTNEY.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to

- (1) Efficient means of closing being provided for all ventilators & air pipes.
- (2) Suitable provisions being made for rigging lifelines which should be available for use in all parts of the vessel which might have to be used by the crew in the regular working thereof.
- (3) The scantlings of the coamings, covers, bearing surfaces, tarpaulins & battening arrangements of any coaling & trimming hatches on the freeboard deck inside the Bridge space being reasonably in accordance with the Convention requirements. The Surveyor should forward full particulars.
- (4) The openings in the ports front being closed with storm boards full height in sweeten channels, as required for the reassignment of the existing freeboard.

The freeboards as computed under the Convention being greater than the existing freeboards, the latter have been reassigned.

CONVENTION.

W497-0133

© 2019  
Lloyd's Register  
Foundation

plus  
22  
18/32

A.S.N.  
1. 8. 33