

FREEBOARD REPORT on the

Ss "CORBEACH"

It is submitted the Freeboards given on the accompanying

form, being those required by the Tables, merit approval, subject to:-

- ① the stowhold gratings being fitted with steel hinged covers where this is not already the case, and all covers being made efficient to the Surveyor's satisfaction.
 - ② the ventilator coverings and air pipes being provided with efficient means of closing
 - ③ gangways, lifelines or other satisfactory means of protecting the crew being fitted in the forward and after wells.
 - ④ the freeing port area on each side of the after bell being increased to $21\frac{1}{2}$ square feet.
 - ⑤ the closing appliances in the bridge after bulkhead having the fastenings made efficient to the Surveyor's satisfaction.
- The Convention Freeboards being in excess of the existing freeboards, the latter have been reassigned.

Convention. Cf/lrs. Owners & Msc. 3/6/32