


COPY



Hong Kong

LLOYD'S REGISTER.

LONDON.

April 19th. 1922.

RECL
ANSO

12 JUN 1922

This is to Certify that

JOHN S. GARDINER

the undersigned Surveyor to this
Society did at the request of

The Owners' Representatives, survey for the computation of the
Deadweight of the British Screw Steamer "PETRICOLA" of Hong Kong,
5818.86 Tons Gross, built by the Hong Kong & Whampoa Dock Company
Limited.

From the particulars supplied by the builders and the
information obtained by the undersigned when this vessel was in
dry dock and subsequently afloat on February 26th. 1922, the
following figures are the result of this investigation:-

Vessel afloat in Kowloon Dock.

| | | | |
|---------------|--------|------------|--------|
| Draft Forward | 3'-2" | Density | 35.10 |
| Draft Aft | 15'-1" | Mean Draft | 9'-1½" |

Corresponding Displacement in Salt Water = 3894 Tons

Items to be added or deducted to complete vessel

| | <u>Tons to be added</u> | <u>Tons to be deducted</u> |
|----------------|-------------------------|----------------------------|
| Mooring Wires | - | 2½ |
| Cement | - | 2 |
| Oil | - | 3 |
| Tar and Boxes | - | 1½ |
| Rubbish | - | 2 |
| Bilge Water | - | 2 |
| Owners' Stores | - | 35 |
| Staging | - | 2 |

Total weight to be deducted 50 Tons

W504-0070 1/2

© 2020

Lloyd's Register
Foundation

S. S. "PETRICOLA"

(2)

Total weight to be deducted 50 Tons

3894 Tons

Finished light weight 3844 Tons

Load Displacement on

Lloyd's Summer Freeboard 6'-9 $\frac{1}{2}$ "

Load Draft Bottom of Keel 24'-8 $\frac{1}{2}$ " 12174

Actual Salt Water Deadweight 8330 Tons

John S. Gardner

SURVEYOR TO LLOYD'S REGISTER

Survey fee - - - - - \$400.00



© 2020

Lloyd's Register
Foundation

W504-0070 2/2

Referred to the Chief Ship Surveyor,

[Signature]

12 JUN 1922

Reported to Mr. Magné.

00.004\$ - - - \$100.00

Handwritten note:
1000000 2. 1000000

0001 0000

0001 0000

{

48.12 48.12

Handwritten text: 1000000 2. 1000000

Handwritten text: 1000000 2. 1000000

0001 0000

0001 0000

00 1000

Handwritten text: 1000000 2. 1000000

Handwritten text: 1000000 2. 1000000

(2)



© 2020

Lloyd's Register Foundation

Handwritten text: 1000000 2. 1000000