

Port of H U L L.

28th February, 19 40.

# REPORT ON MASTS, SPARS, AND RIGGING.

Dear Sirs,

Having, in accordance with your instructions,  
examined the Masts, Spars, Iron Work of same, and Rigging, of the  
(Name of Vessel) s.s. "LULONGA"

on the (Date of examination) 27th February, 19 40,

I have to report that I found Fore top mast stay in good condition.  
rigging screw to anneal and shackle to renew. Fore stay good. Rigging  
screw and shackle anneal. Top mast back stay good. Rigging screw to  
renew. Fore port shroud to renew, Star'd in good condition. All rigging  
screws to be overhauled. Fore top mast to renew. Fore main mast in  
good condition.

MIDDLE MAST, port main preventer stay good. Rigging screw to renew.

" top mast stay fair. Screw to overhaul.

" fore shroud good.

" middle shroud to renew. All screws to be annealed


" aft shroud to renew. and new bolts as required.

" back stay in good order.

Fee £ - : 10 : -

To the Surveyors,  
Lloyd's Register of Shipping,

H U L L.



© 2021

Lloyd's Register  
Foundation

W 51-0189(112)



Star'd top mast stay good. screw to anneal.

" main mast stay good. screw to renew.

" shrouds fore. - fair.

" " Middle - fair.

Screws to be annealed bolts

" " aft - renew.

renew as required.

Top mast in good order.

Main mast 4' from bottom required compensation plate.

Aft Mast. Mast and all rigging good.

Star'd aft rigging screw to renew. remainder to be annealed.

Top mast good.

Funnel guys and scress in good condition.



© 2021

Lloyd's Register  
Foundation

W 51-0189(2b)