



"LULONGA"Now Done. Damage. Repairs effected :-

- H.P. Bottom end re-metalled, Steering Engine Valve chest liner renewed.  
 Main Steam pipes, stripped, annealed, tested to test W.P. & re-lagged.  
 Main Condenser. Tubes withdrawn, cleaned, rightly fit new tubes & ferrules, claud up & tested.  
 Main feed, bilge, circulating, & air pump rods skinned, new gland & neck bushes.  
 New feed suction & delivery Valves, main Engine pumps.  
 New main injection valve, seat, & spindle.  
 Ballast Pump. One new rod. Steam valves & ferrules machined, new steam rings.  
 Feed Donkey pump. New rods, & valve spindle, & new steam rings.  
 Main Boilers. New door joints.  
 Other minor repairs effected.

- L.M.C. Vessel in dry dock. Propeller, sternbrush, oil gland, & outside fastenings, & sea connections, examined, found or placed in satisfactory condition.  
 Screwshaft drawn, examined & found satisfactory.  
 An examination made of main engine, cylinders, pistons, slide valves, main & bottom end bearings, crankshaft complete, thrustshaft, block, & shoes, intermediate shafts, main engine attached pumps & auxiliary pumps, the valves, cocks, pipes, & strainers of pumping arrangements.  
 The main steam pipes, & auxiliary steam pipes over 3" bore, examined & hydraulically tested, to rule requirements & found in good order.  
 Main Condenser, examined, & after re-lubricating, tested.  
 All electric circuits, dynamo, tuggar tested, & found or placed in good order.  
 Dynamo Governor tested & found satisfactory.  
 All machinery tried out under working conditions on completion & found satisfactory.  
 B.S. Boilers examined in their entirety, together with safety valves & mountings, all found or placed in good order.  
 Boilers examined under steam, & safety valves adjusted to above stated pressure.

Repairs effected :-Owner's A/c

- L.P. slide valve spindle, skinned, new gland & neck bushes.  
 H.P. " " " " " new gland & n.m. & new neck bush.  
 Main engine Cylinder & Valve cage bored out, new piston, rings, & piston valve.  
 Other minor repairs carried out.

- S. Boiler. New main check valve spindle.  
 • Blow Down Valve.  
 " Dynamo master steam stop valve spindle.  
 " main stop valve cover.

- P. Boiler. New auxiliary stop valve spindle.

Other minor repairs on both boilers effected.



© 2021

Lloyd's Register  
Foundation

W 57-0192(2/2)