

of Cardiff.

15th August 1919.

James R. Main,

Ministry of Shipping, and acting on instructions received
from the Committee of Lloyd's Register, survey the German Steamer
T. S. S. "ADOLPH VÖRMBACH".

6257 tons gross, of Hamburg.

the purpose of ascertaining her present condition together
with equipment.

In company with Captain Roberts and Mr. Cheke, Chief
Surveyor, representing the Managing Owners, and Mr. G. Evans,
Surveyor to the Norske Veritas Society, the undersigned examined
vessel, whilst lying afloat in the Queen Alexandra Dock,
Cardiff, and in the Mount Stuart Dry Dock, Cardiff, on the
June 1919, and on subsequent dates.

The Classification papers were examined and it was noted,
that vessel is classed in the Germanischer Lloyd's as follows:-

100 A.L. (E) +  March 1918.

 M.C. March 1918.

Vessel now placed in Dry Dock. Bottom and rudder cleaned

© 2020



Lloyd's Register

WSTOUT00304

S. S. "ADOLPH VOERMAN".

-2-.

examined and recoated. Cables ranged. Bilge keel (P & S.) more or less slightly buckled. No.3 plate, from aft, in 4th Strake below Sheer, port side, "indented", but not dealt with.


Examination was made of forward peak spaces, after peak tank and spaces over, double bottom tanks, holds, 'tween decks, I. & B. spaces, tank top plating under boilers, chain locker, upper and lower coal bunkers (as far as practicable), Decks, casings, hatch coamings covers and supports, masts, rigging, derricks, boats, winches, windlass steering gear and connections, spaces under Poop, Bridge and Forecastle and general equipment.

Holds:- Ceiling fitted on Tank top throughout. In Nos 1-4 5 holds close ceiling fitted on ship's side to 'tween decks. In nos. 2 & 3 holds sparring and cleats fitted on ship's side. Limbers now part lifted and bilges examined. Bilges in Nos 3-4 & 5 holds now cleaned. All double bottom tanks examined internally, now coated and broken cement in No.1 renewed. Tank top plating under Boilers examined and found in good condition. Wood sheathing on tunnel worn in way of hatches. Ladders in Nos 2 & 3 holds bent - now repaired.

'Tween Decks:- Sparring and cleats fitted on ship's side in nos 1-2 & 3 tween decks. Close ceiling fitted on ship's side in nos. 4 & 5 tween deck. In No.4 tween deck, hatch coaming scored through with wire and bottom flange of hatch beam irregular and hafted by wire.

Coal Bunkers:- Lower and Upper bunkers partially examined. Gross bunkers now scaled and coated.

Deck fittings etc:- Derricks overhauled and spars, guys etc., renewed as necessary.



© 2020

Lloyd's Register
WS 10 Footation

"ADOLPH WOERNMANN".

-3-

ther decks recaulked and payed where necessary. Steering chaine swed and sheaves overhauled. Rollers in fairleads freed and pins swed. Windlass overhauled, spare bow anchor and kedge freed made workable. All ventilators overhauled and repaired where necessary. Baths & W.C.s overhauled and put in order.

Appment:-

Anchors on board Three Bowers, One Stream, One Kedge.

Cables ranged 270 fathoms 2½" diameter.

Four 2" Manilla Hawser 120 fms. each (supplied at Leith).

Two 2" " " 120 " " (supplied at Cardiff).

One 2½" wire about 100 fms.

One 3" " " 60 fms.

One 3" " " 90 fms.

One 3" " " 120 fms.

Two 3" " " 120 fms (supplied at Cardiff).

One 3½" " " 90 fms.

One 3½" " " 120 fms.

Boats examined by Board of Trade Surveyors and placed to their requirements. Two extra lifeboats now put on board.

All internal work is well coated and is a satisfactory condition.

:- Tween decks now fitted out for carrying troops and 18" tional sidelights cut in sheerstrake, of similar size to those ready in ship.

In my opinion, so far as I can judge, from my inspection the parts of the vessel which have been examined, the vessel appears to be in a fit condition to run for a period of six months.

WS10-00303/4

© 2020
J. R. Mann, Surveyor to Lloyd's Register
Lloyd's Register Foundation

culars of the Steel Twin Screw Steamer "ADOLPH WOERNLIAN".

ers. Reinerstieg. Schiffswerfte.

Hamburg. 1906.

Weermann Line.

Hamburg.

sions by Classification Certificate.

l. 125.38 metres.

ith. 15.45 metres.


L. 8.77 metres.

s tonnage. 6257 tons.


r deck. 4362 tons.

3909 tons.

sed in Germanischer Lloyd's



March 1913.



March 1913.

Creatonial. Forecastle, Combined Bridge and Poop.

Promenade and Boat Deck.

Two complete decks, i.e. Main and Lower Decks, with Orlop Deck
ending from Stem to aft end No. 1 Hold.

ular double bottom throughout and after Peak Tank.

ent Managing Owners.

Gee, Thomson & Co., Ltd. LONDON.

of Registry.

LONDON.

A stylized signature of the name "J. R. L. Main".
SURVEYOR TO LLOYD'S REGISTER.

© 2020



Lloyd's Register
W5601-0030/4