

31st March

20.

NORMAN DOBSON,

the shipping agent representative survey the German surrendered steamer "ADOLPH WUNDERMAN", 2257 tons gross, whilst lying in Tilbury Dry Dock on the 17th March 1920 and subsequent dates, for damage stated caused by collision with the U.S. "GOLDEN PLE" in the River Thames on the 17th March 1920.

For further particulars see ship's log book.

On examination the undermentioned:

FOUND.RECOMMENDED.

On starboard side amidships one plate in sheerstrake indented.

To be faired in place.

One plate in 5th strake below sheerstrake fractured.

To be renewed.

One plate in 6th strake below sheerstrake fractured.

To be cropped and part renewed, and double buttstraps fitted.

Two plates in 4th below, one plate in 5th, and two plates in 6th strake below sheer indented.

To be faired in place.

Frames from 94 to 99 inclusive indented.

To be cropped and part renewed and efficient straps fitted.

Hold stringer in way of above fractured.

One plate and shell connection angle to be renewed.

Sideplate of screen bulkhead buckled.

To be renewed.



© 2020

Lloyd's Register

WS10-0104 Foundation