

12th January 1923.

782 SHIP.

PRELIMINARY FREEBOARD PARTICULARS.

Builders Dimensions :- 262'0" x 39'3" ext. x 21'0".

Length on L.W.L. :- 261'6½".

Sheer at stem.	7'7½".	} These dimensions are given above lowest point, which is 5/8" below depth moulded. Lowest point is 13'0" aft amidships.
" ½L abaft stem	4'1".	
" Bridge front	5½".	
" ½L before stern	2'4½".	
" stern	4'6½".	

Approximate under deck tonnage - 1527.

Displacement co-ef. .767.

Approximate tons perinch 20.

Breadth of upper deck gunwale 37'11".

Round of beam 9½".

Upper deck not wood covered.

Poop 20'7" x 7'6" high.

Bridge 46'4½" x 7'6" "

Forecastle 21'0" x 7'6" "

Freeing port area in wells to rule.

Engines amidships.

Bridge front of steel without openings.

Bridge end of steel with channels and boards.

Forecastle front of steel with channels and boards.

Poop front of steel without openings.

Crew berthed in poop.

*Bent's Bend 35"*

*No Beiling*

*" Sparring (Collies)*

*Frame 8"*

*Draper Tackle*



© 2020

Lloyd's Register  
Foundation

WSA-0078