


Lloyd's Register of Shipping,

Empire House, Mount Stuart Square,

ENCLOSURES.

Cardiff, 7th March, 1934.



Dear Sir,

With reference to the Freeboard Assignment for the steamer "ARIADNE PANDELIS", we beg to report that the conditions of assignment have been carried out as follows:-

- (1) The wood hatchway covers of all hatches on the freeboard and superstructure decks have been placed in good order, and new ones supplied where missing to the Surveyor's satisfaction.
- (2) One tarpaulin provided for each of Nos. 2 & 3 hatchways on the freeboard deck.
- (3) Covers, one tarpaulin and efficient battening arrangements provided for each of the escape scuttles and small coaling hatchways on the freeboard deck inside the bridge space.
- (4) One ventilator coaming on the starboard side of the bridge deck, and one coaming in the after well renewed. One scuttle coaming and cover on the starboard side of the casing top removed and an efficiently bolted plate fitted over opening.
- (5) Efficient means of closing have been provided for all air pipes.
- (6) Suitable provision made for rigging lifelines which are available for use in all parts of the vessel which might have to be used by the crew in the regular working thereof.
- (7) Minor repairs have been effected to the engine room skylight flaps, the port side stokehold grating cover, one hinged cover on the donkey boiler house top, the rails and stanchions on the forecastle head, the rods of the freeing ports and the locks and handles of the doors in the exposed machinery casings.

- (8) The openings in the machinery casings in way of the coal shoot have been closed by bolted plates, bolts spaced 6" centres.
- (9) Two rest bars have been fitted to the small hatchway on the poop deck, bearing surface $2\frac{1}{2}$ ".

The old freeboard certificates are returned herewith for ~~cancel~~ cancellation and the Convention Certificate and certified copy handed over.

We are, Dear Sir,


Yours faithfully,

The Surveyors,

per:-

J. J. Campbell

The Secretary,
LONDON.



© 2020

Lloyd's Register
Foundation

W512 - 0379(212)

Referred to the Chief Ship Surveyor.
(Freeboard).

E

- 8 MAR 1934

*Particulars of alterations noted on
report.
Sents waived.*

*P.B.B.
8/3/34.*

Re: -

the following

the following

the following

the following

the following

the following

the following

the following

- 5 -

the following

© 2020
Lloyd's Register
Foundation

Dear S

forward

"ARIADN

The Se

L