

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey

Date of Survey

Name of Surveyor

12/4/32

| | | | | | | | |
|---|-------------------------|--|---|---|---|--|--|
| Ship's Name. ITALIAN PRINCE. | | Port of Registry and Nationality. Liverpool British | | Official Number. 146637 | Gross Tonnage. ✓ | Date of Build. 1921. | Particulars of Classification. + 100 A1 Shelter Dk with freeboard. |
| Number in Register Book | | | | | | | |
| Registered dimensions from Ship's Register. | LENGTH. 363.3 | BREADTH. 52.15 | DEPTH. 22.35 | UNDER DECK TONNAGE. 2894.25 | Moulded Depth as measured..... 24'-9" | | |
| Length on LOADLINE. | 363.0 | Frame Depth // Rule 5 1/2 x 2. | Ceiling fitted Sheer -1.16 | Peak Incl. Tanks Increased depth of C.O.B. for 2 aft + 1/5 | Addition for Keel below base line for draught record..... inches. | | |
| Connected DIMENSIONS. | 363.0 | 51.40 | 21.19 | 2942.25 | CORRECTION FOR LENGTH. | | |
| Co-efficient of fineness..... .452 | | Any modification necessary [Para. 4 (a) to (e)]* - .02 C.O.B. | | Co-efficient as corrected43 | | Length of Ship on Loadline..... 363.0 | |
| | | | | | | Length in Table 294.0 | |
| | | | | | | Difference 66.0 | |
| | | | | | | Correction for 10ft., Table A. 1.3 Table C. | |
| | | | | | | × Difference divided by 10 8.58 (if required.) | |
| | | | | | | If 1/10ths length covered divide by 2 4.29 + 4.29 | |
| | | | | | | CORRECTION FOR IRON DECK. | |
| | | | | | | Proportion covered, if less than 1/10ths length covered | |
| | | | | | | Thickness of usual wood deck, less stringer - 3 1/2" | |
| | | | | | | CORRECTION FOR ROUND OF BEAM. | |
| | | | | | | Breadth at Gunwale amidships..... 52'-0" | |
| | | | | | | Round of Beam 1'-1" | |
| | | | | | | Normal round..... 1'-1" | |
| | | | | | | Difference nil ÷ 2 = nil | |
| | | | | | | Proportion of Deck uncovered (Para. 19) | |
| | | | | | | Freeboard, Table A 5'-4" | |
| | | | | | | Correction for Sheer + 10 1/2" | |
| | | | | | | 6'-2 1/2" | |
| | | | | | | Correction for Length + 4 1/4" | |
| | | | | | | 6'-6 3/4" | |
| | | | | | | Allowance for Deck Erections 3'-6 1/2" | |
| | | | | | | 3'-0 1/4" | |
| | | | | | | Correction for Round of Beam..... | |
| | | | | | | Correction for fall in Sheer (if any)..... | |
| | | | | | | Correction for Steel Deck (if required) - 3 1/2" | |
| | | | | | | 2'-8 3/4" | |
| | | | | | | Additions for non-compliance with provisions of { | |
| | | | | | | Para. 11 (d) and (e) ‡ { | |
| | | | | | | Other Corrections (if any) ✓ | |
| | | | | | | Winter Freeboard 2'-8 3/4" | |
| | | | | | | Summer Freeboard 2'-4" | |
| | | | | | | Indian Summer Freeboard 1'-11 1/4" | |
| | | | | | | N.A. Winter Freeboard ✓ | |
| | | | | | | Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. nil | |
| | | | | | | Winter Freeboard from deck line 2'-8 3/4" | |
| | | | | | | Summer " " " " 2'-4" | |
| | | | | | | Indian Summer " " " " 1'-11 1/4" | |
| | | | | | | N.A. Winter " " " " ✓ | |
| | | | | | | SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:— 2'-3 3/4" | |
| | | | | | | Tropical Fresh Water Line above Centre of Disc ... 10 3/4" Tropical Fresh Water Freeboard ... 1'-5" | |
| | | | | | | Fresh Water Line " " " " ... 6 1/4" Fresh Water " " " " ... 1'-11 1/4" | |
| | | | | | | Tropical Line " " " " ... 4 1/2" Tropical " " " " ... 2'-8 3/4" | |
| | | | | | | Winter Line below " " " " ... 5" Winter " " " " ... ✓ | |
| | | | | | | Winter North Atlantic Line " " " " ... ✓ Winter North Atlantic " " " " ... ✓ | |

15 APR 1932

Im. 2.32

Fresh Water. $\frac{8998}{40 \times 36.18} = 6.22 = 6 1/4"$

RECEIVED
24 APR 1932
RECEIVED
26 APR 1932

RECEIVED
24 APR 1932
RECEIVED
26 APR 1932

Lloyd's Register
Foundation