

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping, and are not to be published in any other form without the consent of the Registrar General of Shipping and Seamen.

Official Number.	Name of Ship.	No., Date, and Port of Registry.	
161,931.	Melmay.	42/1930	Glasgow.

Whether British or Foreign Built.		Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British		Steam Ship Single Screw.	Greenock.	1930	The Greenock Dockyard Co., Ltd., Greenock.	
No., Date, and Port of Previous Registry (if any).		Initial Registry.				
Number of Decks	One & Shelter Deck	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet.	421	Tenths.	4
Number of Masts	Three	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	419	8.3		
Rigged	Schooner	Main breadth to outside of plank	59	2.5		
Stern	Elliptical	Depth in hold from tonnage deck to ceiling at midships	24	7.5		
Build	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards	29	0.3		
Galleries	None	Depth from top of beam amidships to top of keel	27	9		
Head	None	Depth from top of deck at side amidships to bottom of keel	1	2		
Framework and description of vessel	Steel-Cargo	Length of engine room, if any	57	5		
Number of Bulkheads	Six					
Number of water ballast tanks, and their capacity in tons	(Six in D.B. 1360 tons (Fore Peak-190 (After Peak-81					

PARTICULARS OF DISPLACEMENT.	
Total to quarter the depth from weather deck at side amidships to bottom of keel	11025 Tons.
Ditto per inch immersion at same depth	48.80 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).								
No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. - I. H. P. - Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Reciprocating Steam Direct Acting Vertical Quadruple Expansion.	Engines.	Engines.	Engines.	Four			604
		and	and	and	24"			3450
					35"	51"		
					51"			
One	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	73"			12 Knots
	Description: Cyl. Mult. Single Under.			David Rowan & Co., Ltd., Glasgow.				
	Number: Three	British	1930					
	Iron or Steel: Steel							
	Loaded Pressure: 225 lb							

PARTICULARS OF TONNAGE.			
GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	4975.01	On account of space required for propelling power	1994.04
Space or spaces between Decks	--	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	172.81
Turret or Trunk	--		
Forecastle... (Lower-19.8 tons-Upper-96.57 tons)	115.75	These spaces are the following, viz.: Houses in Forecastle & Bridge, and Round & Side Houses on Bridge.	
Bridge space (Houses in)	67.21		
Poop or Break	--		
Side Houses	68.51		
Deck Houses	75.42		
Chart House	6.41		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	263.95	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways	--	Master's Accommodation-17.57 tons	
		Chart Space - 6.41 "	
		Wireless Telegraphy - 2.39 "	
		Boatswain's Store - 28.15 "	
		Water Ballast Spaces - 86.84 "	
		Total ...	2307.21
Gross Tonnage	5572.26	Cubic Metres	15769.50
Deductions, as per Contra	2307.21		6529.41
Register Tonnage	3265.05		9240.09

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 875.50 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 269.90 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Space in Shelter 'Tween Decks,	399.1 feet in length	- 1632.46 Tons.
Open Space in Bridge,	117.5 " " "	- 372.34 Tons.
Open Space in Poop,	23.4 " " "	- 86.68 Tons.

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
The Melmay Shipping Company, Limited, 24, George Square, Glasgow. Sixty-four Shares.	Thomas Lawrie Duff of same address - Manager
Dated 4th September, 1930.	



WS2-0060

Wch - W. Traverson