

Clayd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

 Index No. **22369**
 (For London Office only.)

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

 Port of Survey Barneg
 Date of Survey 25th April 1932
 Name of Surveyor

Ship's Name. AGNES DUNCAN	Port of Registry and Nationality. <u>British Cardiff</u>	Official Number. 132868	Gross Tonnage. 2514	Date of Build. 1912/7	Particulars of Classification. + 100 A.1.
Number in Register Book					
Registered dimensions from Ship's Register.	LENGTH. 306	BREADTH. 43.2	DEPTH. 20.1	UNDER DECK TONNAGE. 2111.14	
Length on LOADLINE.		Frame Depth 10 Rule 5 1/2	Ceiling fitted 15	Peak Tanks	
		4 1/2 x 2 = .75	Tank used at margin	6' Deep floor aft + 20	
CORRECTED	306	42.45	21.179	2131.14	

 Moulded Depth as measured..... **22'-7 1/2"**
 Wood deck less str. **-3 1/2"**
 Addition for Keel below base line **22'-4"**
 for draught record..... inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

Mould depth to use

CORRECTION FOR LENGTH.

Length of Ship on Loadline.....	306	
Length in Table	268	
Difference	38	
Correction for 10ft., Table A.	1.2	Table C. .6
x Difference divided by 10	4.56	(if required.) 2.28
If 1/10ths length covered divide by 2	+4 1/2	+2 1/4

CORRECTION FOR IRON DECK.

 Proportion covered, if less than 1/10ths length covered
 Thickness of usual wood deck, less stringer
Allowed in moulded depth

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....	42'-0"	
Round of Beam	10 1/2	
Normal round.....	10 1/2	
Difference	✓ ÷ 2 =	✓
Proportion of Deck uncovered (Para. 19)		✓

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A	4'-6 1/2"
Correction for Sheer	3
	4'-3 1/2"
Correction for Length	4 1/2
	4'-8"
Allowance for Deck Erections	8
	4'-0"
Correction for Round of Beam.....	✓
Correction for fall in Sheer (if any).....	
Correction for Steel Deck (if required)	<u>allowed in moulded depth</u>
Additions for non-compliance with provisions of Para. 11 (d) and (e) ‡	
Other Corrections (if any)	✓

Winter Freeboard	4'-0"
Summer Freeboard	3'-8 3/4"
Indian Summer Freeboard	3'-5 1/2"
N. A. Winter Freeboard	4'-2"

 Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. **✓**

Winter Freeboard from deck line	
Summer " " " "	
Indian Summer " " " "	
N. A. Winter " " " "	

FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:—		3'-8 1/2"	
Tropical Fresh Water Line above Centre of Disc ...	8	Tropical Fresh Water Freeboard ...	3'-0 1/2"
Fresh Water Line " " ...	5	Fresh Water " " ...	3'-3 1/2"
Tropical Line " " ...	3	Tropical " " ...	3'-5 1/2"
Winter Line below " " ...	3 1/2	Winter " " ...	4'-0"
Winter North Atlantic Line " " ...	5 1/2	Winter North Atlantic " " ...	4'-2"

 F.W. = $\frac{5464}{40 \times 26.4} = 5.11 = 5"$

 MARKING FORM RECEIVED **9 APR 1932**
 MARKING FORM RECEIVED **26 MAY 1932**

W521-0062