

FREEBOARD REPORT on the FERMANAGH

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval. Subject to:-

1. The wood for + afters being steel shod at all bearing surfaces.
2. Efficient closing appliances being provided for all air pipes where these are not already on board.
3. Suitable provision being made for rigging lifelines which should be available for use in any part of the ship which might have to be used by the crew in the regular working of the ship.
4. The freeing port area on the Raised Quarter Decks being increased to 11 sq ft on each side.
5. The ~~doors~~^{fastening} appliances for the doors in the Forecasts, bulblead and the exposed machinery casings being repaired to the satisfaction of the Surveyor.

Surveyor
Competition

Accepted on Beh.
28/1/38