

LLOYD'S REGISTER,
LONDON.LCE MAY 24 1918
NSD

Greenock

21st May 1918.

J James Jones

Dear John & Kincaid the Ld Clyde
Primary Greenock attend at their works,
for the purpose of examining a New High Pressure
Cylinder for the Steel Screw Steamer

"Ville de Arras".

New Kincaid's Engines No 462 now being fitted
on board by Messrs The Londonderry Ship Building
Co Ltd at Londonderry.

Upon the 8th May and subsequent
date the undersigned made the necessary
examination during the boring and machining
of the cylinder, and found with the exception
of a short contraction crack on the bottom lagging
flange on the right hand side close to the bottom
foot, the cylinder was in good condition in all
respects.

The



© 2020

Lloyd's Register
Foundation

WS29-0274 2/2

The slight defect above named,
does not in my opinion detract from the
efficiency of the cylinder, and has now been
electrically welded, such welding being thoroughly
well done. The cylinder was afterwards tested
by hydraulic pressure to 270 lbs per square inch,
and found tight and sound in all respects.

Sept 1-1-0.

Samuel Jones.

Engineer in Charge to Lloyd's Register.
Birmingham.



© 2020

Lloyd's Register
Foundation

Referred to the Chief Engineer Surveyors

MAY 24 1818

Cor

Also for Mr. S. A. Hill to note.

Referred to Mr. Mayne.

255-1

1818
May 24

1818
May 24

1818
May 24

© 2020

Lloyd's Register
Foundation