

Steam Trawler "BOSTANIAN" ex "DRAGON ROUGE"

Dimensions: 130 x 23.5 x 1315

Scantling Number: 1755

Proportions:- 9.6 *Depth to Length*

This vessel was built in 1916 by Messrs. Smiths
to class with the British Corporation
Dock Co. Ltd., and is ^{now} classed with the Bureau Veritas.

The new Owners, The Boston Deep Sea Fishing
& Ice Co. Ltd., are desirous of classing the vessel with this
Society.

Sketches of midship section and profile and deck
have been forwarded by the Liverpool Surveyors.

The scantlings and arrangements as indicated
on the plans have been compared with the Society's Rules
for Trawlers, and are found to be equivalent thereto.

It is submitted that provided the requirements
of the Rules for vessels not built under survey be complied
with, and a favourable report be received from the Surveyors,
the vessel will be eligible to be classed ¹⁰⁰/_A- Trawler.

The equipment indicated on the midship section
has been compared with the Rule requirements, and it is found
that the anchors are as required by the Rules, but that 165
fathoms of 15/16" stud link chain has been supplied instead
of 120 fathoms of 1 1/8" chain. The weight of the cable in the
ship is 75 cwt, while the weight of the cable required by the
Rules is 77 3/4 cwt. *The remainder of the equipment is equivalent to the Rules*

the remainder of the equipment
It is submitted the anchors and chains could be

WS'32-0088 1/2

approved for the figure "1", provided an additional 15 fathoms of 15/16" chain be supplied.

The Surveyors should endeavour to ascertain whether the steel of which the vessel is built has been tested in accordance with the Society's Rules, and should compare the equipment on board with the certificates.

[Handwritten signature]
22.4.29.

[Handwritten initials]

[Handwritten signature]
Dr. 18/4/29
and 23rd
1/plan

[Handwritten signature]
73/4



© 2019

Lloyd's Register
Foundation

WS32-0088 2/2