

# ADVICE NOTE.

Trust Report 8532

CHESTERFIELD,

Advice No. 5404.

Stabilimento Tecnico Triestino Fabbrica

20th February 1929.

Macchine S. Andrea,  
Ufficio Centrale Acquisti,  
TRIESTE (5) ITALY.




TELEPHONE No. 2161 (3 LINES), CHESTERFIELD  
TELEGRAMS: "TUBES, CHESTERFIELD"

From **THE CHESTERFIELD TUBE CO. LTD.**

Your Order No. 2791/4.

Our Order No. 7963/28.

Pipe Nos.	Quantity.	Description.	Length.		Weight.				Marks.	Truck No.
			Feet.	Inches.	Tons.	cwts.	qrs.	lbs.		
		COLD DRAWN MILD STEEL AIR BOTTLES. Lloyds Inspection.								
	2	381 mm o/d x 6.5 mm th. x 2750 mm. Overall.			9	0	24			
		Nos. 176107-8. 206 CNT								
		One end necked down to 200 mm inside diameter, thickened internally to 185 mm diameter, screwed externally 216 mm diameter 8 threads per inch, and fitted with Mild Steel Flange screwed on 370 mm diameter x 60 mm thick, with 8 holes tapped 1 1/8" Whitworth on 300 Pitch Circle Diameter.								
		The opposite end necked down to 200 mm inside diameter, thicken end internally to 185 mm diameter, screwed externally 216 mm diameter 8 threads per inch and fitted with Mild Steel Flange screwed on 370 mm diameter x 60 mm thick, drilled 8 holes 38 mm diameter on 300 mm Pitch Circle diameter. Bottle ends recessed as shown on drawing. Cylinders painted black. IN ACCORDANCE WITH OUR DRAWING No. 3228 C.								
Mark.-		S.T.T.F.M. TRIESTE. Nos. 1 & 2.								
		Planges protected with timber. Weight.-						4 lbs.		



RU Hawcett  
23/2/29

We have this day consigned in good order and condition the above mentioned Goods per L. & N.E.R.

Railway, Carriage

Packed in

loose.

cases

bundles.

To

Alexandra Dock, Liverpool, for shipment per ss "OPORTO". Order of.- Messrs.

G. A. Woodcock, Ltd., 5, Rumbold Street, Liverpool.  
We do not hold ourselves responsible for any Shortage in and/or Damaged Goods unless the Delivery Note is so endorsed before being signed.  
In this event please at once return Advice Note to us with explanatory Memorandum.

W533-0114

THE CHESTERFIELD TUBE CO. LTD.

© 2019

Lloyd's Register Foundation