

Steel Screw Steamer "KIRISHIMA MARU" built by The
Fujinagata S.B. Co. of Osaka in 1916.

Rule Dimensions: 272 x 40 x 24.17

Scantling Numbers 64.17 & 17454.

Proportions: Length = 11.25 Depths.

The Kobe Surveyor states that the Owners of this vessel, Messrs. Matsuda Kisen Gomed Kaisha, which was built by the Fujinagata S.B.Co. in 1916, desire that this vessel should now be classed in the Society's Register.

The plans and report forwarded by the Surveyor have been examined and it is found that provided the Main deck sheerstrake be doubled full width for about 20 ft. at the ends of the bridge, unless it be found that the sheerstrake is already increased in thickness or other equivalent means of strengthening has been provided at these parts, the equipment be found in accordance with or equivalent to the Society's Rules; and a favourable report be received from the Society's Surveyor, the vessel will be eligible to be classed 100A1.

Provided always that the Engines & Boilers are found to be in good condition & in accordance with the Rules.

The Surveyor should be informed by wire accordingly.

C.F.
C.C.
B.C.
R.R.K.

26.10.16.

Lr. 31.10.16.



© 2020

Lloyd's Register
Foundation

W536-0350