

30 MAY 1924

No. 28821

Rpt. 13.

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office..... 30 MAY 1924

Date of writing Report 19 When handed in at Local Office 29 MAY 1924 Port of SUNDERLAND

No. in Survey held at SUNDERLAND. Date, First Survey 22 May 24 Last Survey 19
Reg. Book. "City of Salisbury" (Number of Visits.....)
on the Tons { Gross 5946.39
Net 3794.07
Built at Sunderland By whom built Wm Gray & Co Ltd Yard No. 955 When built 1924
Owners Ellerman Line Ltd (Hall Line Ltd managers) Port belonging to Liverpool
Electric Light Installation fitted by Wm Gray & Co Ltd. Contract No. When fitted 1924

System of Distribution Double ✓ volts, Heating — volts, Power —
Pressure of supply for Lighting 100 ✓
Direct or Alternating Current, Lighting Direct ✓ Power —
If alternating current system, state frequency of periods per second
Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes ✓
Generators, do they comply with the requirements regarding overload yes, are they compound wound yes ✓
are they over compounded 5 per cent. yes, if not compound wound state distance between each generator
Where more than one generator is fitted are they arranged to run in parallel is an adjustable regulating resistance fitted in series with each shunt field yes
Are all terminals accessible and clearly marked yes, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited yes
Position of Generators Engine Room Recess yes, are they clear of all inflammable material yes
is the ventilation in way of the generators satisfactory yes, state distance of same horizontally from or vertically above the generators
if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators yes
and —, are the generators protected from mechanical injury and damage from water, steam or oil yes
are their axis of rotation fore and aft yes are the prime movers and
Earthing, are the bedplates and frames of the generating plant efficiently earthed yes
their respective generators in metallic contact yes
Main Switch Boards, where placed Near Dynamo
If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard yes
Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes
are they protected from mechanical injury and damage from water, steam or oil yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards and
are they constructed wholly of durable, incombustible non-absorbent materials yes, is all insulation of high dielectric strength and of permanently high insulation resistance yes, if semi-insulating material is used, are all conducting parts connected to one pole insulated from the slab with mica or micanite and the slab similarly insulated from its framework, and is the frame effectively earthed yes
Are the following fittings as per Rule, viz.: — spacing or shielding of live parts
accessibility of all parts yes, absence of fuses on back of board yes, proportion of omnibus bars 1 1/2" x 3/8" COPPER, individual fuses to voltmeter, pilot or earth lamp yes, connections of switches yes
Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches
For Generator 1 Double pole knife switch & double pole fuse
Each outgoing Circuit 1 Single pole, 1 knife switch & double pole fuses.
Instruments on main switchboard 1 ammeters 1 voltmeters synchronising device for paralleling purposes. Lamp.
Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system
Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules yes.
Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule yes.

ENC. 30 MAY. 1924

Insulation of Cables, state type of cables, single or twin *Single* are the cables insulated and protected as per Tables III or IV of the Rules *yes*.

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *none*.

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets *yes*.

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound.

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *yes*.

Support and Protection of Cables, state how the cables are supported and protected *Steel armored & braided clipped to deck*.

If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armored and lead covered cables are secured by metal clips, are the clips spaced as per Table VI *yes*.

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements.

Joints in Cables, state if any, and how made, insulated, and protected *none*.

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *yes*.

Bushes in Beams and Non-watertight Positions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *yes*. state the material of which the bushes are made *fibre*.

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *Dynamo bolted to steel deck*
Switch box frame bolted to steel bulkhead
are their connections made as per Rule *yes*.

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *yes*.

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven.

Navigation Lamps, are these separately wired *yes*, controlled by separate switch and separate fuses *yes*, are the fuses double pole *yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *yes*, has each navigation lamp an automatic indicator as per Rule *yes*, are separate screens provided for the use of oil and electric side lights *yes*, are separate oil lanterns provided for the mast head lights and side lights *yes*.

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *yes*, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *yes*, are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *none*, how are the cables led *yes*, where are the controlling switches situated.

Searchlight Lamps, No. of —, whether fixed or portable —, are their fittings as per Rule —.

Arc Lamps, other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —.

Motors, are their working parts readily accessible —, are the coils self-contained and readily removable for replacement —, are the brushes, brush holders, terminals and lubricating arrangements as per Rule —, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material —, are they protected from mechanical injury and damage from water, steam or oil —, are their axis of rotation fore and aft —, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —, if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —.

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed as per Rule —.

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule —.

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings —.

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office —.

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Amps.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN	1	20	100	200	300	Charles Chapman			
AUXILIARY						Vertical open type			
EMERGENCY						Single cylinder 8" dia 8" stroke			
ROTARY TRANSFORMER									

LIGHTING AND HEATING CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR...	2	0.24680	37	0.093	90	48 feet	Rubber	Braid & Compound
	AUXILIARY GENERATOR	—							
	EMERGENCY GENERATOR	—							
	ROTARY TRANSFORMER...	—							
	AUXILIARY SWITCHBOARDS	—							
	ENGINE ROOM	2	0.00701	7	0.036	14	30 feet	Rubber	Steel Arm & Lead
	BOILER ROOM	2	0.00194	3	0.029	3	100 feet	"	" " "
	Saloon	2	0.00701	7	0.036	16	200 feet	"	Lead Arm & Braid
	Engineers	2	0.00701	7	0.036	12	80 "	"	" " "
	WIRELESS	2	0.002214	7	0.064	15	120 feet	Rubber	Lead Arm & Braid
	SEARCHLIGHT	—							
	MASTHEAD LIGHT...	2	0.00194	3	0.029	2	220 "	"	Lead Arm & Braid
	SIDE LIGHTS	2	0.00194	3	0.029	2	50 "	"	Lead & Arm
	COMPASS LIGHTS	2	0.00194	3	0.029	5	25 "	"	Lead & Arm
	POOP LIGHTS	2	0.00701	7	0.036	10	280 "	"	Lead Arm & Braid
	CARGO LIGHTS	2	0.00701	7	0.036	8	85 "	"	Lead Arm & Braid
	ARC LAMPS	—							
	HEATERS	—							

MOTOR CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
The foregoing is a correct description.

FOR THE WEAR SHIPYARD

W. B. Shaw

Electrical Engineers.

Date 24th May 1924

COMPASSES.

Distance between electric generators or motors and standard compass 190 Feet

Distance between electric generators or motors and steering compass 180 "

The nearest cables to the compasses are as follows:—

A cable carrying 5 Ampères 25 feet from standard compass 20 feet from steering compass.

A cable carrying 15 Ampères 40 feet from standard compass 35 feet from steering compass.

A cable carrying 30 Ampères 180 feet from standard compass 175 feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power.

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted

The maximum deviation due to electric currents was found to be degrees on course in the case of the standard

compass, and degrees on course in the case of the steering compass.

FOR THE WEAR SHIPYARD

W. B. Shaw

Builder's Signature.

Date 24th May 1924

Is this installation a duplicate of a previous case If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c.)

As far as seen this installation has been fitted in a satisfactory manner and in accordance with the rules.

The vessel has left this Port for Harthpool to have machinery installed. To complete survey on Electric light installation, the wiring in E, B space remains to be carried out and the installation tried under working conditions. Harthpool Surveyors advised.

It is submitted that
this vessel is eligible for
THE RECORD. Elec. light.

W. B. Shaw
4/7/24

Total Capacity of Generators 20 Kilowatts

The amount of Fee ... £ 17:10 : 26 MAY 1924

Travelling Expenses (if any): £

When received,
L. de B. book

Ex. H. K. R.

Surveyor to Lloyd's Register of Shipping.

Committee's Minute

TUES. 8 JUL 1924

Elec. Lt.

Assigned

Im. 3.22.—Transfer.
(The Surveyors are requested not to write on or below the space for Committee's Minute.)



© 2020
Lloyd's Register
Foundation