

BOARD REPORT on the

## SS "Himadale Castle"

It is submitted the Southampton Surveyors be informed that the moulded draught of this ship estimated in this office is as follows:-

moulded depth :	42 - 6"
Stringer plate	$\frac{1}{2}$ "
Wood sheathing	3"
	<hr/>
	42 - 9 $\frac{1}{2}$

Summer freeboard.

	13 - 11"
	<hr/>
	28 - 10 $\frac{1}{2}$

Summer moulded draught.

It is also estimated that the addition for keel and garboard plates is about 3 inches, making the extreme summer draught to be 29 - 1  $\frac{1}{2}$ . The Surveyors should, therefore, verify the figure of 29 - 11 given in their letter of yesterday's date and report to this office.

W 542 - 00 89

21-7-32

5.  
2  
2  
10  
52  
- 4  
45  
+  
46  
46  
+ 2  
16  
67  
" "