

FREEBOARD REPORT on the

*S.S. "Eugenia".*

A freeboard of 6'-0" was assigned to this vessel when she was built in January, 1906, but in June of that year an amended freeboard of 5'-9½" was assigned in accordance with the revised regulations and this freeboard is still in force.


The writer's representative produced a general arrangement plan and displacement scale which were supplied by the Builders when the vessel was completed. This showed a load draught in summer of 23'-8" which agrees with the records in this office.

It is submitted the writer be informed that the present freeboard amidships is 5'-9½" from statutory deck line 1¾ inches above Shell Spar deck at side, corresponding to a summer draught of 23'-10½". The winter draught is 5 inches less.

Representative calling  
at 3 p.m. for answers.

*W.C.D.*

*H. G. 95*



© 2020

Lloyd's Register  
Foundation  
W545-0164