





and the following repairs now carried out  
 Keel plate N<sup>o</sup> 1 with doubling plate and outer strip removed faired & replaced  
 SB; A strake plate N<sup>o</sup> 1 ..... faired in place  
 II strake plate N<sup>o</sup> 6 removed and 2 frames faired in place  
 P.S. B strake plate N<sup>o</sup> 1 & 2 removed faired and replaced  
 B strake plate N<sup>o</sup> 3 removed and 3 frames faired in place  
 Bulge keel SB and PS over about 27 ft. length removed  
 faired and replaced

One topside plate in counter on SB faired in place  
 Deck stringer L and half round in way of same removed  
 faired and replaced

Rolling profile which stanchions in way of same  
 faired in place

Rudder cleaned and found in good condition and recoated  
 Ventilator coamings examined and found good.

One of the bower anchors with stock see first Entry report N<sup>o</sup> 11354 has been  
 replaced by a bower stockless as below.

Particulars of stream anchor verified, found as below

All anchors having been tested as per Rule

Chain cables certificates verified, found in order and issued by G.L. have  
 been sent here with for your consideration, in order to have vessel  
 clasped with the figure I in case it could meet your

When Anchors or Cables are supplied, the particulars are to be reported in the following form:—

Equipment Letter **D+**

#### ANCHORS.

Number of Certificate.	Anchors.*	WEIGHT, EX. STOCK.			WEIGHT OF STOCK.			TEST, PER CERTIFICATE.			WEIGHT REQUIRED by TABLE 30 or 31.			Description of Anchor.	Makers.	Where and when tested and Superintendent.
		Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.	Tons.	Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.		
14671	1st Bower ...	68	2	14	✓			53	1	3	14			stockless	W.L. Byers & Co.	L.P.H.S. 15/8 1916
	2nd "														H. Ltd.	L. Hoffmann
	3rd "															
	Collective Weight.															
41523	Stream .....	40	0	0	✓			35	10	3	0			stockless		L.P.H.N.
	Kedge.....															

\* When a bower anchor is supplied it must be clearly stated whether it is a 1st, 2nd, or 3rd bower.

on anchor no Certificate to hand

#### CHAIN CABLES.

Number of Certificate.	Length and size supplied.		Test per Certificate.		WEIGHT OF CHAIN CABLE.		Length and size per Table 30 or 31.		Description.	Makers of Cables.	When and where tested and Superintendent.
	Length.	Diam.	Statutory.	Breaking.	Supplied.	Per Table 30 or 31.	Length.	Diam.			
	Fathoms.	Ins.	Tons.	Tons.	Cwts. qrs. lbs.	Cwts. qrs. lbs.	Fathoms.	Ins.			
Iron Stream Chain or Steel Wire...											

approval, and anchors being made to rule requirements

H. J. Parker