


G.R. 130.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) G.P.P.J.



Official Number.	Name of Ship.	No., Date, and Port of Registry.
167227	BRITISH INFLUENCE	89 in 1939 London

No., Date, and Port of previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Motor Ship Single Screw	Newcastle-on-Tyne	1939	Swan Hunter & Wigham Richardson Ltd., Newcastle-on-Tyne, 6.

Number of Decks One	Length from fore part of stem, to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts Two	...	466	3
Rigged Not	Main breadth to outside of plating	61	9
Stem Straight	Depth in hold from tonnage deck to ceiling amidships ...	33	9.5
Stern Cruiser	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	-	-
Build Clencher	Depth from top of deck at side amidships to bottom of keel	34	2.7
Framework and description of vessel Steel Cargo	Round of beam	1	3
Number of Bulkheads Watertight - Twelve	Length of engine room, if any	75	-

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N.H.P. B.H.P. L.H.P. Estimated Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Internal Combustion Opposed Piston Type Vertical	British	1939	Swan Hunter & Wigham Richardson Ltd., Newcastle-on-Tyne, 6.	Four	Upper Piston 980 m.m.	-	687
One	Particulars of Boilers.	Boilers.	Boilers.		600 m.m.	Lower Piston 1340 m.m.	-	2850
						23 5/8	Total 2320	9 1/2

Number of water ballast tanks, and their capacity in tons :- Four = 880 Tons.

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	7409.63	On account of space required for propelling power	2697.91
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew	
Turret or Trunk		These spaces are the following, viz. :-	533.14
Forecastle		Bridge, Poop - Deck Houses.	
Bridge space Houses in	81.25	(Number of Seamen or Apprentices for whom accommodation is certified 45 (or 58 including 39 lascars).)	
Poop or Break	263.54	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-	
Side Houses	4.44	Chart Space 7.96	
Deck Houses	357.66	Masters Accommodation 33.07	
Chart House		Wireless Space 5.84	
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	314.45	Boatswains Stores 70.43	344.69
Excess of Hatchways		Ballast Pump Spaces Total 39.50	
		Water Ballast Spaces 187.89	3575.74
Gross Tonnage	8430.97		
Deductions, as per contra	3575.74		
Register Tonnage	4855.23		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 783.13 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 314.45 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle	L. 64.7'	= 152.59 Tons.
Overhang F.E. Bridge	L. 4.5'	= 21.29 "
" F.E. Poop	L. 3.5'	= 15.99 "
Open Bridge Space	L. 36.0'	= 67.98 "
Open Passageways	L. 10.05'	= 8.51 "
A.E. Forecastle	L. 5.70'	= 14.19 "
Overhang A.E. Bridge	L. 3.0'	= 14.31 "

Name of Master Certificate of Service No. Competency No.


No. of Owners Name, Residence, and Description of Managing Owner if there are more owners than one.

British Tanker Co. Ltd., Britannic House, Finsbury Circus, London, E.C.2.

Manager: James Ross Robertson of same address.

Shares: Sixty-four.

Dated 18th April, 1939.



W560-0126

W560-0128

GENERAL REMARKS—(The Surveyor should state the Number of Report and Name of any Sister Vessel.
The Plans should be embodied.)

Plans showing Vessel as built should be forwarded and a List of

Ms Boden



© 2020
Lloyd's Register
Foundation

RECEIVED 2019

PART
SPECIAL
PARTICULARS
Cast Steel
Weight,
Number
of Test.
PARTICULARS
(in f
Official No.
No. and M
Parts of Bot
PARTICULARS
Double bottom
Double bottom
Double bottom
Double bottom
Total length

Date
Order for Spec

RP
Date
No.
Reg.
Don
Eng
Bair
SSB
Given
1037