

Messrs. Helsingbergs Varvs. & Svetsnings A.B.No.54.

Dimensions:- 246' x 38' x 17.5': Class: 100A1 "Strengthened
for navigation in Ice".

A telegram has been received from the Helsingberg
Surveyer giving particulars of the weights of the anchor
equipment, and asking if the stream anchor can be approved.

The weights of the anchor equipment as required by
the Rules, and as proposed to be supplied are given in the
following table:-

	RULE			PROPOSED TO BE SUPPLIED.		
	cwts.	qrs.	lbs.	cwts.	qrs.	lbs.
Bower anchors (steckless) collective weight	87	0	0	88	1	14
Stream anchor	7	3	0	5	3	24
Stream anchor steck	1	3	21	1	3	4
	96	2	21	96	0	14

It will be seen from the above that the stream anchor,
including steck, is 280 lbs. lighter than required by the Rules,
and that, even allowing for the heavier weight of the bower
anchors, the collective weights of all anchors is 63 lbs. less
than required by the Rules.

In these circumstances it is considered that a stream
anchor of the correct weight should be supplied, and it is
submitted the Helsingberg Surveyer be informed accordingly,
be cable.

Feb. 13/02
Anch. 14/02 (2el. 8lbs)

14.8.31

W561-0182