

400'-0" x 52'-0" x 32'-1½" D.M.

SHELTER DECK.

STRINGER PLATE $60 \times \frac{11-8}{20}$
" ANGLE $3 \frac{1}{2} \times 3 \frac{1}{2} \times \frac{10-7}{20}$
BEAMS ON EVERY FRAME $6 \times 3 \times \frac{8}{20}$ ANGLES. if supported equivalent to 3 rows of pillars.
" AT HATCH ENDS $9 \times 3 \times \frac{12}{20}$ BULB ANGLES
STRONG BEAMS IN ENGINE SPACE $9 \times 3 \times \frac{12}{20}$ BULB ANGLES.
STEEL DECK $\frac{7-6}{20}$
SHEETER DECK.

N^o 260. *x* 261

FLOORS FLANGED TOP AND BOTTOM $\frac{10-9}{20}$ $\frac{10}{20}$ UNDER ENGINES FLANGED AT BOTTOM $\frac{10}{20}$ UNDER BOILERS $\frac{11}{20}$

TANK INTERCOSTALS FLANGED TOP AND BOTTOM $\frac{9}{20}$

VERTICAL LUGS ON FLOORS $\frac{3}{20} \times \frac{3}{20} \times \frac{9}{20}$

ALL PARTS INCREASED $\frac{1}{20}$ IN BOILER SPACE

NO KEEL DOUBLING

Lloyd's Register
Foundation
W563-0163

RETAIN

Jenners. Worthy & Co

N^o 260. S.S. Slotendyk

Copy of Midship Section

Hpl. Report No. 11784



© 2020

Lloyd's Register
Foundation

W563-0163