

C. 7c.11.28.

FREEBOARD REPORT on the

S. S. BRITISH COMMERCE.

It is submitted the Freeboards given on the accompanying

form, being those required by the Tables, merit approval, *Subject to*

The wood doors in the forecastle bulkhead leading to spaces below the freeboard deck being replaced by steel doors, capable of being manipulated from both sides.

The bulkheads in the forward & after wells being cut away & replaced by open rails as per plan submitted.

The shifting boards closing the openings in the bridge after bulkhead being specially supported in view of the width of the opening unless these boards are at present at least 3" thick.



© 2021
S.F.B.

Lloyd's Register
Foundation

W568-0113

Ass. the Owners
+ Ital
27/5/32

attention

to retain