

W569-0203

8c.131.

FREEBOARD REPORT on the

S.S. "MUREX"

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval. Subject to.


- ① The two ventilators on the Poop deck at present 5'-5" high X being efficiently supported.
- ② Efficient means of closing being provided for all air pipes.
- ③ The two air pipes to the fore cofferdam and two to the after cofferdam being increased in height to 36"
- ④ The bulwarks for 50% of the length of each were being cut away and open rails fitted, or alternatively the freeing port area in the fore well being increased to 108 square feet and in the after well to 87 square feet on each side of the ship. ✓

J. M. M.

18-5-32.

British Convention.
Return Displacement and Tonnage.

Over. Lrs. Owners, 18 5 32.



© 2020

Lloyd's Register
Foundation