

PROVIDING ELBOWS FROM SAME CAST.

1-TENSILE AND 1-BEND TEST ONLY REQUIRED FOR EACH 25 ELBOWS OR UNDER.

IF OVER 25 ELBOWS UP TO ANY NUMBER - MAXIMUM TESTS - 2 TENSILE AND 2 BENDS.

ALL BENDS TO BE TESTED BY HAMMERING.

(THE ABOVE TESTS MEET THE REQUIREMENTS OF LLOYD'S. BOARD OF TRADE & BRITISH CORPORATION,
(FOR SURVEYS REQUIRED - SEE ORDER.)

THE SUPERHEATER CO LTD
BUSH HOUSE LONDON W 6 2

TITLE 3½" ELBOW.

[illegible]

SCALE FULL SIZE.	
DWN.	TCI
St. Louis 1/4/32	