

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Date of writing Report

19

When handed in at Local Office

80 MAR. 1929

Port of

Newcastle-on-Tyne

2 APR 1929

SUNDERLAND

No. in Survey held at Sunderland.

Reg. Book.

Date, First Survey

15.1 Jan

Last Survey

Mch 28 1929

(Number of Visits.....)

on the S. S. "Hlanarth"

Tons

Gross 5089

Net 3042

Built at Sunderland.

By whom built

Bartram & Sons Ltd

Yard No. 265

When built 1929

Owners Pictou S. S. & Co Ltd

Port belonging to

LondonElectric Light Installation fitted by Messrs Campbell & Sherwood & Co Ltd

Contract No.

When fitted 1929.

System of Distribution

Double wire ✓

Pressure of supply for Lighting

110

volts, Heating

—

volts, Power

—

volts.

Direct or Alternating Current, Lighting

Direct

Power

—

If alternating current system, state frequency of periods per second

—

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off

Yes

Generators, do they comply with the requirements regarding rating

Yes

, are they compound wound

Yes.

are they over compounded 5 per cent.

Yes

, if not compound wound state distance between each generator

—

Where more than one generator is fitted are they arranged to run in parallel

—

, is an adjustable regulating resistance fitted in

series with each shunt field

Yes

Are all terminals accessible, clearly marked, and furnished with sockets

Yes

, are they so spaced or shielded that they cannot be accidentally earthed,

short circuited, or touched

Yes

Are the lubricating arrangements of the generators as per Rule

Yes.

Position of Generators

Engine room starboard side

is the ventilation in way of the generators satisfactory

Yes

, are they clear of all inflammable material

Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

—

and

—

, are the generators protected from mechanical injury and damage from water, steam or oil

Yes.

are their axes of rotation fore and aft

Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed

Yes

are the prime movers and

their respective generators in metallic contact

Yes.

Main Switch Boards, where placed

Engine room starboard side

If the generators and main switchboard are not placed in the same compartment, is each generator provided with

a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

—

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes

Yes

are they protected from mechanical injury and damage from water, steam or oil

Yes

, if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards

—

and

—

are they constructed wholly of durable, non-ignitable non-absorbent materials

Yes

, is all insulation of high dielectric strength and of

permanently high insulation resistance

Yes

, if semi-insulating material is used, are all conducting parts insulated from the slab

with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework

Yes

and is the frame effectively earthed

Yes

Are the fittings as per Rule regarding:— spacing or shielding of live parts

Yes

, accessibility of all parts

Yes

, absence of fuses on back of board

Yes

, proportion of omnibus

bars

Yes

, individual fuses to voltmeter, pilot or earth lamp

Yes

, connections of switches

Yes.

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches.

Double pole switch & fuses on dynamo mains. Single pole switch & double pole fuses on each outgoing circuit

Instruments on main switchboard

one

ammeters

one

voltmeters

—

synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

earth lamps coupled to earth through switches & fuses.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules

Yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule

Yes

© 2019

Lloyd's Register
Foundation

W57-0114

Cables: Single, twin, concentric, or multicore single. are the cables insulated and protected as per Tables IV or V of the Rules Yes
Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 4 volts.

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets Yes.

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound Yes.

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes.

Support and Protection of Cables, state how the cables are supported and protected Lead covered & armoured cables in engine room
main cables V.I. Run in screwed steel conduit in tween decks cargo spaces. Lead covered
If cables are run in wood casings, are the casings and caps secured by screws Yes, are the cap screws of brass Yes, are the cables run in separate grooves Yes. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII Yes.

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements None fitted

Joints in Cables, state if any, and how made, insulated, and protected None made

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes. state the material of which the bushes are made Lead.

Earthing Connections, state what earthing connections are fitted and their respective sectional areas are their connections made as per Rule

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule Yes.

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven Yes

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes, are the fuses double pole Yes, are the switches and fuses grouped in a position accessible only to the officers on watch Yes, has each navigation lamp an automatic indicator as per Rule Yes

Secondary Batteries, are they constructed and fitted as per Rule Yes

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight Yes, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected Yes

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected Yes, how are the cables led Yes

where are the controlling switches situated Yes

Searchlight Lamps, No. of Yes, whether fixed or portable Yes, are their fittings as per Rule Yes

Arc Lamps, other than searchlight lamps, No. of Yes, are their live parts insulated from the frame or case Yes, are their fittings as per Rule Yes

Motors, are their working parts readily accessible Yes, are the coils self-contained and readily removable for replacement Yes, are the brushes, brush holders, terminals and lubricating arrangements as per Rule Yes, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material Yes, are they protected from mechanical injury and damage from water, steam or oil Yes, are their axes of rotation fore and aft Yes, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type Yes, if not of this type, state distance of the combustible material horizontally or vertically above the motors Yes and Yes

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule Yes

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule Yes

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings Yes

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office Yes

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	1	10	110	91	400	Single cylinder steam engine		
AUXILIARY								
EMERGENCY								
ROTARY TRANSFORMER								

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR...	2	.1009	19	.083	91	✓ 16	V.I. R	Lead covered & braided
	EQUALISER CONNECTIONS								
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER...								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM	2	.00701	7	.036	18	✓ 6	50	Lead covered & braided
	BOILER ROOM	2	.01046	7	.044	14.8	✓ 96	50	50
	ACCOMMODATION	2	.01046	7	.044	15.6	✓ 160	50	50
	50 saloon	2	.01046	7	.044	15.0	✓ 94	50	50
	WIRELESS	2	.01046	7	.044	15.0	✓ 180	50	50
	SEARCHLIGHT								
	MASTHEAD LIGHT	2	.00194	3	.029	.6	✓ 200	50	in steel pipe
	SIDE LIGHTS	2	.00194	3	.029	.6	✓ 60	50	50
	COMPASS LIGHTS	2	.00194	3	.029	.25	✓ 30	50	50
	STERN LIGHTS	2	.00194	3	.029	.6	✓ 360	50	50
	CARGO LIGHTS	2	.0017	40	.0076	2.0	✓ 120	50	Cable type
	ARC LAMPS								
	HEATERS								

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	(a) MOTOR GENERATOR								
	(b) MAIN MOTOR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
The foregoing is a correct description.

J. Meade.

Electrical Engineers.

Date 26/3/29.

COMPASSES.

Distance between electric generators or motors and standard compass 94 feet.

Distance between electric generators or motors and steering compass

The nearest cables to the compasses are as follows:—

A cable carrying .25 Amperes on the ~~standard~~ standard compass feet from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted yes

The maximum deviation due to electric currents was found to be ~~not~~ degrees on all course in the case of the standard compass, and ~~not~~ degrees on all course in the case of the steering compass.

For Bartram & Sons Ltd.

J.H. Bartram

Builder's Signature.

Date

Director.

Is this installation a duplicate of a previous case yes. If so, state name of vessel Llanwern

General Remarks (State quality of workmanship, opinions as to class, &c.)

The above installation is in accordance with the Society's Rules. The vessel is eligible in my opinion for notation as light wireless.

It is submitted that
this vessel is eligible for
THE RECORD. — ELEC. LIGHT.

YRM

4.4.29

Total Capacity of Generators 10 Kilowatts.

The amount of Fee ... £ 10. : 26 March 29

Travelling Expenses (if any) £ : 15.4.29

W.T. Badger

Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

Elec Light