

Philadelphia, Penna.,

Heavy Weather
No 1

October 11th, 1917

S. S. "CACIQUE"

TWEEN DECK No. 1 HOLD:-

Six thwartship deck beams forward of No. 1 hatch to be cropped, straightened and replaced with suitable buttstraps
 Aft center girder in way of same to be removed, faired and replaced
 Deck beams on starboard side of No. 1 hatch to be removed, faired and replaced, similar with port side
 Aft longitudinal girder on starboard side of hatch to be removed, faired and replaced, similar with port side
 Deck plating in way of above to be pumped back into place and riveted as necessary
 Deck beams on port side of No. 1 hatch to be removed, faired and replaced
 Aft center girder in way of above to be removed, faired and replaced

PORT DECK:- No. 1 HOLD:

Deck beams on port and starboard side of hatch to be removed, faired and replaced
 Deck plating in way of above to be pumped back into place, and riveted as necessary
 Aft longitudinal girders on both sides to be faired in place
 Deck beams on port side of No. 1 hatch to be removed, faired and replaced



© 2020

Lloyd's Register

Foundation

W598-0251