

Rpt. 16.

No. 98225.

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Date of writing Report 26 JAN. 1931 When handed in at Local Office 26 JAN. 1931 Received at London Office 28 JAN 1931

No. in Survey held at Birkenhead Date, First Survey Oct 20th/30 Last Survey 27th Nov 1930
Reg. Book. 89947 on the S.S. "CALDER" (Number of Visits.....)

Built at BIRKENHEAD By whom built CAMMELL LAIRD & CO Yard No. 976 When built 1930
Owners LONDON MIDLAND & SCOTTISH RAILWAY CO Port belonging to Goree
Tons { Gross 1107
Net 445

Electric Light Installation fitted by THE SUNDERLAND FORGE & ENG. CO LTD Contract No. 976 When fitted 1930

Is the Vessel fitted for carrying Petroleum in bulk —

System of Distribution DOUBLE WIRE.

Pressure of supply for Lighting 110 volts, Heating — volts, Power — volts.

Direct or Alternating Current, Lighting DIRECT. Power —

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off YES.

Generators, do they comply with the requirements regarding rating YES, are they compound wound YES.

are they over compounded 5 per cent. YES, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel —, is an adjustable regulating resistance fitted in series with each shunt field YES.

Are all terminals accessible, clearly marked, and furnished with sockets YES, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched YES Are the lubricating arrangements of the generators as per Rule YES.

Position of Generators MAIN ENGINE ROOM.

is the ventilation in way of the generators satisfactory YES, are they clear of all inflammable material YES.

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators — and —, are the generators protected from mechanical injury and damage from water, steam or oil YES.

are their axes of rotation fore and aft YES.

Earthing, are the bedplates and frames of the generating plant efficiently earthed YES. are the prime movers and their respective generators in metallic contact YES.

Main Switch Boards, where placed MAIN ENGINE ROOM.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes YES

are they protected from mechanical injury and damage from water, steam or oil YES., if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —

are they constructed wholly of durable, non-ignitable non-absorbent materials YES., is all insulation of high dielectric strength and of permanently high insulation resistance YES., if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micamite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework YES.

and is the frame effectively earthed YES. Are the fittings as per Rule regarding:— spacing or shielding of live parts YES, accessibility of all parts YES., absence of fuses on back of board YES., proportion of omnibus bars YES., individual fuses to voltmeter, pilot or earth lamp YES., connections of switches YES.

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches MAIN DOUBLE POLE SWITCH & FUSES FOR GENERATOR. DOUBLE POLE SWITCHES & FUSES FOR OUTGOING CIRCUITS.

Instruments on main switchboard 1 ammeter, 1 voltmeter, — synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system LAMP, SWITCH & FUSE ON EACH POLE CONNECTED TO EARTH.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules YES.

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule YES.



W615-0245 1/2

Cables: Single, twin, concentric, or multicore SINGLE & TWIN are the cables insulated and protected as per Tables IV or V of the Rules YES.

Fall of Pressure, state maximum between bars and any point of the installation under maximum load 4.0.

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets YES.

Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound —.

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage YES.

Support and Protection of Cables, state how the cables are supported and protected CABLES IN ENGINE ROOM SUPPORTED BY GALV. IRON CLIPS AND IN ACCOMMODATION BY BRASS CLIPS. CABLES:- LEAD COVERED & BRAIDED.

If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII YES.

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements —.

Joints in Cables, state if any, and how made, insulated, and protected NONE MADE.

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands YES.

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed YES state the material of which the bushes are made FIBRE & LEAD.

Earthing Connections, state what earthing connections are fitted and their respective sectional areas —.

are their connections made as per Rule —.

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule YES.

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven —.

Navigation Lamps, are these separately wired YES, controlled by separate switch and separate fuses YES, are the fuses double pole YES.

are the switches and fuses grouped in a position accessible only to the officers on watch YES.

has each navigation lamp an automatic indicator as per Rule YES.

Secondary Batteries, are they constructed and fitted as per Rule YES.

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight YES.

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected —.

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected —.

how are the cables led —.

where are the controlling switches situated —.

Searchlight Lamps, No. of —, whether fixed or portable —, are their fittings as per Rule —.

Arc Lamps, other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —.

Motors, are their working parts readily accessible —, are the coils self-contained and readily removable for replacement —.

are the brushes, brush holders, terminals and lubricating arrangements as per Rule —, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material —.

are they protected from mechanical injury and damage from water, steam or oil — are their axes of rotation fore and aft —.

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —, if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —.

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule YES.

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule —.

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings —.

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office —.

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN ...	1	10	110	90.9	350	16 1/2 IP STEAM ENGINE		
AUXILIARY ...								
EMERGENCY ...								
ROTARY TRANSFORMER								

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR ...	1	.1	19	.083	90.9	118	65	V.I.R.	L.C & BRAIDED.
EQUALISER CONNECTIONS ...									
AUXILIARY GENERATOR ...									
EMERGENCY GENERATOR ...									
ROTARY TRANSFORMER MOTOR GENERATOR ...									
ENGINE ROOM ...	1	.01	7	.044	11.1	31	65	V.I.R.	L.C & BRAIDED.
BOILER ROOM ...									
AUXILIARY SWITCHBOARDS ...									
SALOON NAV. & FOR ^o	1	.0145	7	.052	13.7	37	230	V.I.R.	L.C & BRAIDED.
OFFICERS & ENGIN ^{rs}	1	.007	7	.036	8.3	24	100	V.I.R.	L.C & BRAIDED.
POOP CREW ACCOMM ^o	1	.007	7	.036	8.3	24	150	V.I.R.	L.C & BRAIDED.
AFT CARGO & HOLD L ^{ts}	1	.007	7	.036	8.7	24	75	V.I.R.	L.C & BRAIDED.
FOR ^o CARGO	1	.01	7	.044	10.9	31	150	V.I.R.	L.C & BRAIDED.
ACCOMMODATION ...									
WIRELESS ...									
SEARCHLIGHT ...									
MASTHEAD LIGHT ...	1	.002	3	.029	36	4.8	350	V.I.R.	L.C & Braided
SIDE LIGHTS ...	1	.002	3	.029	36	4.8	80	V.I.R.	L.C & Braided
COMPASS LIGHTS ...	1	.002	3	.029	18	4.8	30	V.I.R.	L.C & Braided
POOP LIGHTS ...									
CARGO LIGHTS ...									
ARC LAMPS ...									
HEATERS ...									

MOTOR CONDUCTORS

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP ...										
MAIN BILGE LINE PUMPS ...										
GENERAL SERVICE PUMP ...										
EMERGENCY BILGE PUMP ...										
SANITARY PUMP ...										
CIRC. SEA WATER PUMPS ...										
CIRC. FRESH WATER PUMPS ...										
AIR COMPRESSOR ...										
FRESH WATER PUMP ...										
ENGINE TURNING GEAR ...										
ENGINE REVERSING GEAR ...										
LUBRICATING OIL PUMPS ...										
OIL FUEL TRANSFER PUMP ...										
WINDLASS ...										
WINCHES, FORWARD ...										
WINCHES, AFT ...										
STEERING GEAR—										
(a) MOTOR GENERATOR ...										
(b) MAIN MOTOR ...										
WORKSHOP MOTOR ...										
VENTILATING FANS ...										

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description.

P. PRO THE SUNDERLAND FORGE & ENGINEERING CO. LTD.

Electrical Engineers.

Date Jan. 8th 1931.

COMPASSES.

Distance between electric generators or motors and standard compass —

Distance between electric generators or motors and steering compass 100 FEET.

The nearest cables to the compasses are as follows:—

A cable carrying .18 Ampères — feet from standard compass 10 feet from steering compass.

A cable carrying .36 Ampères — feet from standard compass 10 feet from steering compass.

A cable carrying — Ampères — feet from standard compass — feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power —/es

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted —/es.

The maximum deviation due to electric currents was found to be — degrees on — course in the case of the standard compass, and — degrees on — course in the case of the steering compass.

GAMMELL LAIRD AND COMPANY LIMITED.

J. W. Laird Builder's Signature.

21 JAN 1931

Date

Is this installation a duplicate of a previous case *no* If so, state name of vessel ✓

General Remarks (State quality of workmanship, opinions as to class, &c.)

This Elec light installation has been fitted under special Survey and is in accordance with the Rules requirements. It has been examined under full working conditions & found satisfactory and is eligible in my opinion for record of Elec light in Register book

It is submitted that this vessel is eligible for THE RECORD.

Electric light

J. W. Laird

Total Capacity of Generators 10 Kilowatts.

The amount of Fee ... £ 10 0 0

When applied for, 9/12/30

Travelling Expenses (if any) £ :

When received, 31/12/30

J. Philton

Surveyor to Lloyd's Register of Shipping.

Committee's Minute LIVERPOOL 27 JAN. 1931

Assigned

Electric Light



© 2020

Lloyd's Register Foundation

Im. 11.29.—Transfer.
 (The Surveys are requested not to write on or below the space for Committee's Minute.)