

# Lloyd's Register of Shipping.

Merchants' Exchange, Bute Street,

Cardiff, 3rd. May 1921.

3 ENCLOSURES.

LLOYD'S REGISTER  
LONDON

RECEIVED 4 MAY 1921

INSD

9/5/21

*ackd*

S.S. "ANGERMANALFVEN".

Sir,

With reference to your letters of 21st. and 28th. Ultimo, we beg to forward herewith freeboard report (Form 11b.) with a view to freeboard assignment; also two approved plans (longitudinal and midship section), and an amended longitudinal sketch showing alterations previously effected at after part of No.2. Hatch, and two additional bulkheads now fitted (No.85 W.T. No.55 not W.T.).

As the poop (formerly shelter deck) scuppers etc., are found permanently closed, and additional accommodation is now being fitted in fore part of poop space, Owners' attention has been drawn to deficient height of coamings on No.4. poop deck hatch (formerly over tonnage well).

Some damage repairs, and S.S.No.2. for classification (Section 48.) are now well advanced, and will be reported on completion.

The Equipment of Anchors and Chains on board has been examined, and found as follows:-



© 2020

Lloyd's Register  
Foundation

W619-0103 1/2  
W619-0103 2/2

-2-

			<sup>c</sup>			Test.
1st. Bower.	L.P.H.B.C.	10211	27-3-0	Taylor's	Stockless	26.18.00.
2nd. "	"	10212	27-2-7	"	"	26.16.00.
3rd. "	"	10213	23-2-0	"	"	23.10.00.

---

Collective weight. 78-3-7.

---

Stream Anchor.	L.P.H.B.C.	10214	8-0-0, 2-0-0	Common	<sup>c</sup> 10-2-2-0.
Kedge	"	10215	3-2-14, 0-3-21	"	<sup>c</sup> 6-0-0-0.

All made by S. Taylor & Sons, but original Certificates not available.

Chain Cables.

205 fms. (375 metres) x  $1\frac{9}{16}$ , tests  $43\frac{18}{20}$   $61\frac{8}{20}$ , weight <sup>c</sup>257-0-0.

L.P.H.B.C. 14655, Made by S. Taylor & Sons.

Stream wire, 112 fms.  $3\frac{1}{2}$ "; also hawsers and warps.

Owners request to be informed (as soon as practicable) whether same will be approved for Figure 1.

We are, Sir,

Yours faithfully,

THE SURVEYORS,

per

*[Signature]*

The Secretary.

LONDON.



© 2020

Lloyd's Register  
Foundation

W65-0103 2/2

Referred to the Chief Ship Surveyor.

ram.

-4 MAY 1921

*[Handwritten signature]*



© 2020

Lloyd's Register  
Foundation