

178

S.S. "ANGERMANALEVEN" ex-German Steamer.

---

This vessel built in 1914 by Messrs. Lindholmens V.A., Gothenburg, was classed with the Germanischer Lloyd and is now at Cardiff undergoing survey with a view to classification with this Society.

Plans of the main boilers have now been submitted for consideration.

The scantlings as shewn on plan meet the requirements of the Rules for the original working pressure of 12.6 kilogrammes per square centimetre, with the exception of the furnaces, the thickness of which, owing to the minimum tensile strength, is slightly below the Rule thickness.

It is submitted that provided the boilers be opened out and examined; the furnaces be found to shew no sign of strain, and the boilers otherwise be in good order and safe working condition and their scantlings in accordance with the plan, they might be accepted for the original working pressure of 12.6 kilogrammes per square centimetre (say 180 lbs. per square inch).

The Cardiff Surveyors should be advised accordingly and be requested to forward particulars of the cylinders, shafting, diameter of propeller, and to state whether the screw shaft is fitted with a continuous liner or otherwise. A plan of the pumping arrangements, if obtainable, should also be forwarded.

Return book of plans.

28.4.21

*M.G.*  
27. 4.21.



© 2020

Lloyd's Register  
Foundation

W619-0106