

gpc  
STEEL SCREW STEAMER "TREDENHAM" EX "FALKENFELS" 8

Rule dimensions:- 476.7 x 62 x 35.75 to upper deck  
x 44.75 to bridge deck

This vessel is similar to the "WEISSENFELS" which has received the consideration of the Committee on the 25th ultimo. The above ex German Steamer, previously classed with the Germanischer Lloyd is now under survey at Cardiff, with a view to classification with this Society, at the request of the present Owners Messrs. Hain Steamship Co.

The vessel is of a length to require eight watertight bulkheads, but from the sketch of profile submitted, together with the particulars indicated on the First Entry Report, it is found that six watertight bulkheads only are fitted, two watertight bulkheads, one in the forward, and one in the after hold, being dispensed with. It is submitted that provided suitable structural compensation in the form of additional web frames be fitted in the holds the omission of these two bulkheads might be approved as in the case of the sister vessel referred to, subject to a notation being made in the Register Book on the completion of the survey as follows:-

"Intermediate bulkhead in forward and in after holds dispensed with: 6 B.H. only".

cf.  
31.12.20. BMB

General Committee  
Thursday, 6<sup>th</sup> January, 1921.  
Submission approved



© 2021  
Lloyd's Register  
Foundation