

W631-0159

Steel screw steamer No. 191 ("KEEMUN") building by Messrs. Workman, Clark & Co., Belfast.

This vessel was commenced to the order of the China Mutual Steam Navigation Co., Lim., and has now been taken over by the Ocean Steamship Co., (Alfred Holt) of Liverpool.

Rule dimensions ; 479.9 x 58.0 x 37.0

Equipment number ; 68104

The Owners' Representative wishes to dispense with the 120 fathoms of $5\frac{1}{4}$ " steel wire hawser required in lieu of stream chain, stating that there is no use for it and it is never carried in the other vessels of their fleet (unclassified).

The following are the hawsers required by the Rules, as approved, and as now on board the vessel:-

Rule.	As originally approved.	Now on board.
120 Fms. 1 $6/16$ " stream chain, or $5\frac{1}{4}$ " steel wire.	120 Fms. $5\frac{1}{4}$ " steel wire.	
130 Fms. 6" steel wire.	130 Fms. 6" steel wire.	130 Fms. 6" steel wire.
(Two) 100 Fms. 8" manilla.	(Two) 100 Fms. $2\frac{3}{4}$ " steel wire.	(Two) 100 Fms. $2\frac{3}{4}$ " steel wire.
(Two) 100 Fms. 8" manilla.	90 Fms. 10" manilla.	(Two) 100 Fms. $2\frac{3}{4}$ " steel wire.
	(Two) 90 Fms. 8" manilla.	(Two) 90 Fms. 8" manilla.
		(Two) 90 Fms. 7" manilla.

It is submitted that in order to entitle the vessel to the figure 1, 120 fathoms of 1 $6/16$ " stream chain, or $5\frac{1}{4}$ " steel wire hawser, should be supplied as required by Table 22, or an equivalent thereto should be submitted for the consideration of the Committee.

TUES. 14 OCT 1902

Owner's request approved

13/10/02

Ar. 9.10.02
Armed. 14

Lloyd's Register
Foundation