

Submitted Messrs. A. A. Embiricos & Co. should be informed that the S.S. "MACEDONIA" is built with bulb angle framing and without hold beams. The bulb angle frames are associated with web frames in the forward holds and the engine and boiler space, and are not so deep as they would have been had the web frames not been fitted, although the strength of the combination is at least equivalent. In the after holds the watertight flat at top of tunnels and fresh water tanks serves the purpose for which web frames are fitted elsewhere. As to whether the holds are left sufficiently clear for carrying large marble and machinery, as contemplated by the Owners, is a point upon which this Society cannot express an opinion, this being a matter which can best be determined by the users of the vessel.

3/6/12 C.B. B. C.F.
31.5.12.



© 2020

Lloyd's Register
Foundation