

Shell plates & Butt straps to have a tensile strength
of 26 to 30 tons.

Main stays to have a tensile strength of 27 to 32 tons

other plate max stays " " " 26 to 30 tons.

Donkey Rider for I. O. No 750
to Graydon

Heating surface of tubes	—	482 ft^2
" " " Furnaces	—	55 ft^2
" " " Comb. Chamber	—	86 ft^2
" " " Back Inlet Plate	—	19 ft^2
Total Heating Surface		= 642 ft^2
Grate Surface		= 26.51 ft^2

Nº R 160.

Donkey Boiler


R 160 for

W. Gray & Co. Ltd

No. 750

ss Maylands.

W. Report No. 13350



© 2021

W65-0111

Lloyd's Register
Foundation