

L. O. Coby

CERTIFICATE NO. 443.

April 23rd.1924

Messrs. The Kawasaki Dock Yard (Hiogo Works) Ltd.,

XXX

April 6th.1923 to March 22nd.1924

Six 5" T pieces (LR.4) with branches of different sizes.
Two 5" Escape valve chests (LR-2) with two valves (KS-6)&
(KS-11).

Two 5" Globe stop valve chests (KS-19)&(KS-21)with covers
(LR.4) and valves (KS-30).

Two 5" main "two valve" stop valve chests (KS-13)&(KS-21)with
four covers (KS-6) and (KS-10) and four valves (KS-14)&(KS-19)

Dropped from a height of 10 feet on to hard ground, then
suspended and hammered without indication of defect.

HYDRAULIC TEST:- All tests to three times w.p.= 600 lbs.per sq.in.

| | T/sq.in. | Clamp % in 2" | Band. 1" x 3/4" x 120° |
|-------|----------|------------------|---------------------------|
| KS-6 | 31.14 | 33 | Good. |
| KS-10 | 31.53 | 33 | " |
| KS-13 | 32.46 | 33 | " |
| KS-14 | 32.36 | 33 | " |
| KS-19 | 31.29 | 20 | " |
| KS-21 | 32.43 | 31 | " |
| KS-30 | 35.1 | 20.2 | " |

These castings

of S/S "Raifuku Maru

Superheater steam pipe 1 1/2 in

XXX

Lloyd's Test No. 433 A-V
W.T. 600 lbs. W.P. 200 lbs.
AW LR 22.3.24.

96.00
10.00
Yen 106.00

W. L. L.



© 2020

Lloyd's Register
Foundation

W659-0061