

WORKING PRESSURE = 180 LBS TO LLOYD'S AND DUTCH LAW.

4 BOILERS PER N°

TUBES FOR BLOWERS 3" BORE  $3\frac{3}{4}$ " EXT. DIAM.  
10 THREADS PER INCH  
EFF. AREA = 3.24 SQ. INS.

STEEL STAYS MARKED 'S' ARE  $1\frac{7}{8}$  DIA.  
SCREWED 11 THREADS PER INCH  
EFF DIA = 1.758. EFF AREA = 2.429 SQ IN.

~~WASHER 18" DIAM.  $\frac{15}{16}$  THICK  
18 RIVET HOLES  
 $\frac{3}{4}$  STAY~~





TRATE

James Brown

9/9/13

W 663 - 0024



© 2020

Lloyd's Register  
Foundation