

S. S. No 366

Equipment numeral in accordance
with the new method of obtaining same
per Notice No 1062. —

Plating lumber to Main deck. — ✓

$$143.04 \times 597.84 = 85515.03$$

$$\text{Auming DR.} - 600 \times 0 \times 1\frac{1}{2} = 7200.$$

$$\text{Bridge DR.} - 270 \times 9 \times 1\frac{1}{2} = 3645.$$

$$\text{Upper Br. DR.} - 236 \times 0 \times 1 = 1000.$$

$$\text{Rectums on Up. Br. DR.} - 136 \times 0.5 \times 1 = 1156.$$

$$\text{Equipment numeral} = 99404.03$$

Anchors and Chains &c. 99378

2 Bower Anchors 110 Cwts. Stockless } Collective
1 Bower Anchor 100 " " } lot 336 Cwts.

1 Stream " 44½ " Stockless.

1 Kedge " 19 " 24 Stock!

330 Fathoms 3" Stud Chain cable. ✓

90 " 1¾ " " " for Stream Chain

140 " 7½ Steel wire Towline

150 " 6½ " " Hauler

2 x 130 " 3¾ " " "

100 " 3¾ " " "

100 " 3 " " "

2 x 120 " 0 Manila Hauler.

© 2020

Lloyd's Register
Foundation

James Furman
11.2.04