

PARTICULARS.		
HEATING SURFACE	ZOO TUBES	233.6 sq. ft.
"	3 FURNACES	138.0 sq. ft.
"	3 COM ^b . CHAM ⁸³	184.1 sq. ft.
"	TOTAL	555.7 sq. ft.
GRATE AREA	(5' - 3" WIDE)	49.875 sq. ft.
AREA THROUGH TUBES.		8.65 sq. ft.
RATIO	$\frac{H.S.}{G.A.}$	31.2
"	$\frac{G.A.}{AREA THRO TUBES}$	5.74
STEAM SPACE		275 Cu. Ft.

—ONE STEEL AUXILIARY BOILER THUS FOR N^o 304.—

— SCALE 1" = 1 FOOT. —

Dunsmuir &
Jacksons
Auxiliary boilers
No 3044

180 lbs W.P.

To replace Donkey boiler
of Bloemfontein.

Gls. No. 24612



RECEIVED



W673-0246

© 2020

Lloyd's Register
Foundation