

WOOD STEAMER "WAR SOREL"

-----

It is submitted the Barrow Surveyors be informed that where the washers on the points of the bolts have become slack due to shrinkage of the material and the heads are inaccessible, horse-shoe washers may be driven tightly under the present ring washers and secured in place by a small screw to the wood planking. In the few cases referred to where there are no washers on the points of the bolts if the Surveyors find it impracticable to fit washers and reclinch the bolts they should have the points sawn off flush with the inner surface of the ceiling.

Cf. 24. 5. 19.



© 2021

Lloyd's Register  
Foundation

W678-0073

W678-0074 1/2