

# Lloyd's Register of Shipping.

Order: **449J.**

(Report on Vessel No. \_\_\_\_\_ Port \_\_\_\_\_)

No. **3294.**

## SHIP ~~FORGINGS~~ CASTINGS.


The words FORGINGS or CASTINGS, IRON or STEEL, should be struck out as may be required.

I have to report that the undermentioned ~~XXXXXX~~ Steel ~~XXXXXXXXXX~~ Castings, manufactured by **Messrs. Stahlwerk Krieger** of **Düsseldorf-Oberkassel** for the Vessel No. **212**, being built by **Messrs. Deutsche Werke** of **Kiel** have been inspected by me as set forth below and found to be, so far as can be seen, **2 hawses sound and free from surface defects.**

Mark on Forgings or Castings.

Lloyd's  
No. **83/84.**  
V.S. **29.10.27.**

Düsseldorf 3rd November 1927.




	<del>STEEL</del>	RUDDER FRAME.	STEM.
Material*	<b>Annealed Siem. Mart. Cast Steel</b>	/	
How made	<b>cast</b>		
If annealed	<b>Yes</b>		
Dimensions			
Progress on Inspection	<b>rough turned</b>		
Date when Inspected	<b>29.10.27.</b>		
CASTINGS.			
Tests on Standard Test Pieces.	<b>.798 3"</b>		
Tensile Test—			
Tons per square inch	<b>31,6</b>		
Extension per cent.	<b>29,4</b>		
Cold Bending Test—			
Angle before fracture	<b>120 degr. good</b>		
Drop Test—			
Height from ground	<b>12 feet</b>		
Hammering Test—			
If made according to Rules and found satisfactory	<b>satisfactory</b>		

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

Fee (if any chargeable) £ : :

To be paid at **Düsseldorf.**



\* If of Iron, state whether scrap or puddled Iron. If of Steel, state whether made on the Open Hearth process.